# **Kenhowe Drive Public Right-of-Way Construction Impacts**

Side: EAST

**Limits: Existing Sidewalk at 6415 Kenhowe Drive** 

to 6509 Kenhowe Drive

**Sidewalk Width: 5-Ft** 

**Sidewalk Material: Concrete** Road Width: 26-Ft Curb to Curb

ADDRESS	CONSTRUCTION IMPACTS
6415 Kenhowe Drive	Construct a 5-ft-wide concrete sidewalk that will tie into the existing
	sidewalk and transition from the existing 12-ft greenspace to a 0 to 3-ft
	variable greenspace;
	Remove bushes and landscaping within County's public right-of-way as needed.
6417 Kenhowe Drive	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable
	greenspace;
	Remove and replace the existing concrete driveway apron;
	Remove existing slate leadwalk within County's public right-of-way and replace with concrete;
	The sidewalk will run behind Utility Pole No. 761415-8210;
	Remove shrubs and groundcover landscaping within County's public
	right-of-way as needed.
6421 Kenhowe Drive	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace;
	Remove and replace the existing concrete driveway apron;
	The sidewalk will run behind Utility Pole No. 761415-8423;
	The utility pole guide wires will need to be relocated;
	May need to adjust the Water Meter;
	May need to trim branches to elevate 8' above sidewalk.
6425 Kenhowe Drive	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace;
	Remove and replace the existing concrete driveway apron;
	Remove the existing slate leadwalk within County's public right-of-way and replace with concrete;
	Remove one 14-inch in diameter Crepe Myrtle tree; replacement trees may be planted;
	Remove ground cover landscaping within County's public right-of-way as needed.

The above impacts are based on a preliminary investigation and are subject to change at any time **F** as field conditions warrant.

## Kenhowe Drive, EAST

ADDRESS	CONSTRUCTION IMPACTS
6429 Kenhowe Drive	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable
	greenspace;
	Remove and replace the existing concrete driveway apron;
	Remove the existing slate leadwalk within County's public right-of-way
	and replace with concrete;
	The sidewalk will run behind Utility Pole No. 761415-8537;
	The utility pole guide wires may need to be relocated;
	Sidewalk will run behind the yard drain.
6433 Kenhowe Drive,	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable
work on the side of the	greenspace;
property along Kenhowe	Construct an ADA ramp at the intersection of Kenhowe Drive and Pyle
Drive	Rd;
	Remove and replace the existing concrete driveway apron;
	Remove the existing slate leadwalk within County's public right-of-way
	and replace with concrete;
	Remove bushes and landscaping within County's public right-of-way as
	needed;
	Sidewalk will run behind the yard drain;
	May need to trim branches to elevate 8' above sidewalk;
	May need to adjust the Storm Drain Inlet Top.
6500 Pyle Road, work on	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable
side of the property along	greenspace;
Kenhowe Drive	Construct an ADA ramp at the intersection of Kenhowe Drive and Pyle
	Road;
	May need to remove or trim one or two bushes along the fence within
	County's public right-of-way to allow for sidewalk installation;
	May need to adjust the storm drain inlet top.
Vacant Lot	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable
	greenspace;
	Remove one 44-inch in diameter Red Maple tree; replacement trees may be
	planted.
6509 Kenhowe Drive	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace
	and transition to tie into the existing sidewalk.

The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant;

# **Kenhowe Drive Public Right-of-Way Construction Impacts**

Side: WEST

Limits: Existing Sidewalk 6422 to 6504 Kenhowe Drive

Sidewalk Width: 5 Ft

**Sidewalk Material: Concrete** 

Road Width: 23 FT

ADDRESS	CONSTRUCTION IMPACTS
6422 Kenhowe Drive	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace
	to connect to existing sidewalk;
	Remove and replace concrete driveway apron;
	Remove stone paved leadwalk within County's public right-of-way and
	replace with concrete;
	Remove plants, bushes and landscaping near apron, along curb line and
	within County's public right-of-way as needed for sidewalk installation;
	Remove stone pavers within County's public right-of-way near curb line.
6426 Kenhowe Drive	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable
	greenspace;
	Remove and replace concrete driveway apron.
6430 Kenhowe Drive	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable
	greenspace;
	Remove and replace concrete driveway apron;
	Remove and replace concrete leadwalk within County's public right-of-
	way;
	Remove small garden within County's public right-of-way;
	Remove three Crape Myrtle trees, two 3-inch in diameter and one 5-inch in
	diameter; replacement trees may be planted;
	May need to trim branches to elevate 8' above sidewalk;
	Relocate "15MPH" road sign.
6434 Kenhowe Drive	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable
	greenspace;
	Construct an ADA ramp at the intersection of Pyle Road and Kenhowe
	Drive;
	Remove and replace concrete driveway apron;
	May need to remove bush by driveway;
	Remove three Northern Red Oak trees, one 8-inches in diameter and two
	trees 11-inches in diameter; replacement trees may be planted;
	"Stop" sign may need to be relocated.

The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

## Kenhowe Drive, WEST

ADDRESS	CONSTRUCTION IMPACTS
6500 Kenhowe Drive,	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace
work on the side of the	that will transition to tie into the existing sidewalk at 6504 Kenhowe Drive;
property along Kenhowe	Construct an ADA ramp at the intersection of Pyle Road and Kenhowe
Drive	Drive;
	Remove and replace the existing concrete driveway apron;
	Remove and replace the existing concrete leadwalk within County's public right-of-way;
	Remove three trees, one 1-inch in diameter Tulip Poplar tree, one 10-inch
	in diameter Fringetree and one 12-inch in diameter Northern Red Oak; replacement trees may be planted;
	Remove bushes and landscaping within County's public right-of-way as needed;
	The sidewalk will run behind the Pepco Utility Pole No. 761415-6651; the guide wires may need to be relocated;
	May need to adjust the storm drain inlet top.
6504 Kenhowe Drive	Remove the existing concrete and asphalt driveway apron and replace in concrete;
	May need to remove up to 10-ft of the existing concrete sidewalk.
	Remove one 2-inch in diameter Overcup Oak tree; replacement trees may be planted.

The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

## **Pyle Road**

### **Public Right-of-Way Construction Impacts**

**Side: Southeast** 

**Limits: Kenhowe Drive to entrance of Merrimack Pool** 

Sidewalk Width: 5-Ft

Sidewalk Material: Concrete Road Width: 26-Ft Curb to Curb

ADDRESS	CONSTRUCTION IMPACTS
6434 Kenhowe Drive,	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft greenspace;
work on the side of the	The sidewalk will stop near the entrance to the Merrimack Pool;
property along Pyle Road	Construct an ADA ramp;
	Remove three Northern Red Oak trees, one 8-inch in diameter and two 11-
	inch in diameter; replacement trees may be planted;
	Adjust the existing Manhole cover.
6500 Pyle Road, work on	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace;
side of the property along	Construct an ADA ramp at the intersection of Kenhowe Drive and Pyle
Kenhowe Drive	Road;
	Remove one 10-inch in diameter Fringetree; replacement trees may be
	planted;
	May need to remove one or two bushes along the fence to allow for sidewalk
	installation;
	May need to adjust the storm drain inlet top.

The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.