

# Central Avenue/Oakmont Avenue

## Public Right-of-Way Construction Impacts

Side: East  
 Limits: Paradise Court to Railroad Street  
 Sidewalk Width: Five Feet  
 Sidewalk Material: Pervious concrete

LOCATION	CONSTRUCTION IMPACTS
206 Central Avenue	Construct an approximately three foot high concrete block wall at back of sidewalk Construct a five foot wide pervious concrete sidewalk abutting new concrete curb and gutter Construct 15 foot COG inlet and tie to existing pipe Construct Type "K" inlet and tie to new COG inlet with 18 inch HDPE pipe Remove and relocate mailbox <i>Temporary Easement required for block wall construction</i>
206-298 Central Avenue	Construct five foot wide pervious concrete sidewalk abutting new concrete curb and gutter Remove existing W-beam barrier and replace with new W-beam barrier Reconstruct and stabilize existing outfall with new end section and riprap <i>Temporary Easement required for sidewalk construction</i> <i>Perpetual Easement required for drainage structures</i>
16998-17098 Oakmont Avenue	Construct five foot wide pervious concrete sidewalk abutting new concrete curb and gutter Remove existing W-beam barrier and replace with new W-beam barrier Reconstruct existing cross culvert outfall with new end section Construct COG/COS through inlets Stabilize all new outfalls with riprap  @ MARC crossing: install handicap ramp to meet current ADA Standards <i>Temporary Easement required for sidewalk construction</i> <i>Perpetual Easement required for drainage structures</i>

 The above impacts are based on a preliminary investigation and are subject to change at anytime as field conditions warrant