



MD 650 (NEW HAMPSHIRE AVENUE)

MD 650 (NEW HAMPSHIRE AVENUE)

Install curb and gutter. Tie to existing curbs on either side of New Hampshire Avenue Service Road.

Tie to existing sidewalk

NEW HAMPSHIRE AVENUE SERVICE ROAD

Install 5' wide concrete sidewalk

Remove/trim existing vegetation as necessary

Tie to existing sidewalk

9613

9615

9701

9611

