# 401 Hungerford Drive Garage -- No. 500705

Category Subcategory Administering Agency Planning Area

General Government County Offices and Other Improvements **General Services** 

Rockville

Date Last Modified Required Adequate Public Facility Relocation Impact

Status

January 05, 2010

No None.

**Preliminary Design Stage** 

# **EXPENDITURE SCHEDULE (\$000)**

Cost Element	Total	Thru FY09	Est. FY10	Total 6 Years	FY11	FY12	FY13	FY14	FY15	FY16	Beyond 6 Years
Planning, Design, and Supervision	827	3	409	415	317	98	0	0	0	0	0
Land	0	0	0	0	0	0	0	0	0	0	0
Site Improvements and Utilities	220	0	0	220	109	111	0	0	0	0	0
Construction	3,902	0	0	3,902	1,743	2,159	0	0	0	0	0
Other	459	0	0	459	311	148	0	0	0	0	0
Total	5,408	3	409	4,996	2,480	2,516	0	0	0	0	0
		F	UNDING	SCHED	JLE (\$00	0)					
G.O. Bonds	5,408	3	409	4,996	2,480	2,516	0	0	0	0	0
Total	5,408	3	409	4,996	2,480	2,516	0	0	0	0	0
		OPERA	TING BL	DGET IN	IPACT (\$	(000	_				
Energy				-48	0	-5	-10	-11	-11	-11	]
Net Impact				-48	0	-5	-10	-11	-11	-11	

#### DESCRIPTION

The project provides for the design and construction of the rehabilitation of the 401 Hungerford Drive parking garage. The concrete decks in the three story garage are experiencing moderate to severe deterioration. A study completed in June 2005 recommended the removal and replacement of the deteriorated concrete, removal and installation of new expansion joints, repair of the stair tower cracking, new lighting, seismic reinforcement, stormwater management improvements, application of a traffic bearing membrane, concrete sealer and improvements to the small parking lot.

## **ESTIMATED SCHEDULE**

Design is underway and will be completed in Spring of FY10, followed by approximately four months for bidding with a construction period of about seventeen months.

### **COST CHANGE**

The cost increase is due to the addition of construction funding.

#### **JUSTIFICATION**

The parking garage has been in service since 1986. The two upper decks of the garage and access ramps are in poor condition and have experienced moderate corrosion of the structural steel and related detenoration, spalling, and the ponding of water. As of March 2005, 17 percent of the top deck and 13 percent of the middle deck were delaminated or spalled. The structural slabs are in poor condition due to long term infiltration of water and road salts which continue to deteriorate the concrete and corrode the embedded steel reinforcement. There is significant deterioration of the ramp to level 3. The soffit is spalling in some areas due to the migration of water through the unsealed construction joints and cracks in the decks. The garage does not meet current code requirements for stormwater management or seismic events according to the "Existing Condition Appraisal Report" by Walker Parking Consultants, June 2005.

# OTHER DISCLOSURES

APPROPRIATION AND

**County Council** 

- A pedestrian impact analysis has been completed for this project.

EXPENDITURE DATA			Department of General Services	
Date First Appropriation	FY09	(\$000)	Department of Health and Human Services City of Rockville	- FINCOLINAVE
First Cost Estimate Current Scope	FY11	5,408	WSSC PEPCO	1 1
Last FY's Cost Estimate		732	WMATA	NONTH ST 355 Q HOWARD AVE
Appropriation Request	FY11	4,630		
Appropriation Request Est.	FY12	46		
Supplemental Appropriation Re	quest	0		
Transfer		0		
Cumulative Appropriation		732		BEAUL AVE
Expenditures / Encumbrances		7		
Unencumbered Balance		725		WOODER
Partial Closeout Thru	FY08	0		W MIDDLE LA EMBOLE LA PARTIE
New Partial Closeout	FY09	0		X
Total Partial Closeout		0		MONROETE
			0_1	

COORDINATION