



Rehabilitation of Brookville Road Bridge No. M-0083 over CSXT Railroad

PUBLIC MEETING

September 7, 2022





PURPOSE OF THE MEETING

- Introduce project team
- Present the existing bridge and conditions
- Present project scope and property impacts
- Present maintenance of traffic during construction
- Present current project cost estimates, funding and schedule
- Obtain community input

PROJECT TEAM

Montgomery County Department of Transportation (MCDOT)

Barry Fuss
 Bridge Design Chief

Greg Hwang
Project Manager

Brian Copley Construction Section Contract Unit Acting Chief

Eric Willis Property Acquisition Section Chief

Matt Johnson Bike Specialist

Doug Baker Utility Coordinator

Stella Igbinedion Work Zone Program Manager

M-NCPPC Montgomery County Planning Department (MCPD)

Stephen Aldrich Master Planner - Transportation

Jacobs Engineering Group Inc.:

John Truscello Project Manager


Mohamed Ahmed Project Engineer

Eric Gonizke Civil Engineer

Todd Eckhart Structural Engineer

Suhasini Kilim Traffic Engineer

PROJECT LOCATION




LOCAL MASTER PLANS, SPEED LIMIT, TRAFFIC DATA

- 2017 Greater Lyttonsville Sector:
 - 2-Lane Minor Arterial Road MA-3 with 80' Minimum Right-of-Way
- 2018 Montgomery County Bicycle Master Plan:
 - Shared use path (SUP) on the south side
- Posted Speed Limit:
 - * 25 MPH
- Wednesday, November 3, 2021 Traffic Data:
 - \$ 11,500 vehicles/day Average Daily Traffic (ADT)
 - Heavy Vehicles: 2,366 (1,080 during 6-9 AM and 1,286 during 4-7 PM)
 - Pedestrians: 26 during 6-9 AM and 21 during 4-7 PM
 - Bicycles: 1 during 6-9 AM and 2 during 4-7 PM

EXISTING BRIDGE

- ◆ Built in 1976
- 123'-6" long 3-span steel rigid frame concrete deck structure
- ◆ 50-foot clear roadway with two 19'-6" travel lanes and one 11'-0" center left-turn lane
- A 7'-0" concrete sidewalk and a 1'-0" concrete parapet on both sides
- ♦ 66'-0" out-to-out bridge width
- Supported by concrete abutments and pier pedestals.



EXISTING BRIDGE AND APPROACHES



Looking North – Bird's Eye View

1. Concrete Deck

- Minor edge spalling along deck joints
- Failed patch on concrete deck surface
- Torn compression
 joint seals with lost
 adhesion and
 depressed
- High chlorides within top 2" detected by corrosion and chloride testing









2. Steel Frames and Bearings

- Pack rust, minor-tomoderate corrosion, delamination and local distortion at girders, piers, floor beams and bearings
- Non-discernable
 cracking detected by
 ultrasonic examination
 at girder pin-and hanger connections
 and pinned pier
 bearings assemblies













3. Concrete Abutments

- Delamination, spalling and minor honeycombing and cracking at the bearing pedestals
- Spall along top of abutment backwalls









4. Concrete Slope Protection

- Cracks, spalls and delamination at the top of slope protection
- Slightly sliding and local undermining





5. Approach Roadway Asphalt Pavement

Moderate-to-severe cracking






PROJECT SCOPE

Bridge Rehabilitation

- Reconstruct concrete deck to accommodate the Bicycle Master Plan
 - 41' clear roadway w/
 Two 11' travel lanes,
 Two 6' shoulders &
 7' striped median
 - 9' sidewalk on north side
 - 14' shared use path on south side
 - 1'-2 ¼" parapet on both sides
 - 66'-4 ½" out-to-out superstructure




- Repair steel frames and bearings and remove pack rust
- Repair concrete abutments and slope protections
- Approach Roadway Work between Talbot Avenue and Warren Street
 - Construct asphalt new pavement or resurfacing for roadways
 - Construct new concrete curb and gutter, and asphalt shared use path
 - Construct new W-beam or concrete barriers

REHABILITATED BRIDGE AND APPROACHES



Looking North - Bird's Eye View

PROPERTY IMPACTS



MAINTENANCE OF TRAFFIC DURING CONSTRUCTION

All Traffic Maintained thru the Bridge without Detour


Construction Phases: Two Stages

Construction Duration: 15-18 Months

Vehicular Traffic: Two-way Two-lane (10' Lanes, 1' Buffers)

Bicycle Traffic: Shared Road via Travel Lanes

Pedestrian Traffic: Separated Walkway



CURRENT PROJECT COST ESTIMATES, FUNDING AND SCHEDULE

Project Status:

Preliminary Design Stage (30% Level of Completion)

Project Funding

Federal Funds 80%

Montgomery County 20%

Project Cost Estimates

\$ \$800,000 Engineering Cost (Funded)

\$1.8M Construction and Construction Management Cost
 (Not Funded)

Project Schedule

Design Complete Fall 2025

Begin Construction Spring 2026

End Construction Summer 2027

NEXT STEP AND COMMUNITY INPUT

Proceed with Final Design based on

- Comments from permitting agencies:
 - MDOT State Highway Administration
 - M-NCPPC Montgomery County Planning Department
 - Montgomery County Department of Transportation
 - Montgomery County Department of Permitting Services
 - CSX Transportation
- Feedback from the community thru October 7, 2022, by:
 - Tonight's feedback
 - Online comment form: https://forms.office.com/g/sqGUBVNk7q
 - Email to <u>Greg.Hwang@montgomerycountymd.gov</u>

For Project Information

Contact MCDOT's project manager:

Greg Hwang, P.E.

Phone: 240-777-7279

Email: Greg.Hwang@montgomerycountymd.gov

Access MCDOT's project webpage:

QUESTIONS?