

North High Street Extension Facility Planning Study

Alternative Analysis Summary

	No-Build (Existing Conditions)	Alternative 1	Alternative 2
Description	Intermittent sidewalk on the south side, non-ADA compliant; no vehicular connection to Morningwood Drive.	11-foot travel lane in both directions which extends through to Morningwood Drive. A continuous sidewalk on the south side of the street.	11-foot travel lane in both directions which extends through to Morningwood Drive. Pedestrian facilities and parking spaces on both sides of the street.
Utilities	None	8 Electric poles 3 Light poles	11 Electric Poles 3 Light poles
On-Street Parking	Approx. 11 spaces	9 spaces	16 spaces
Street Trees	None	5 Trees	15 Trees
Number of Properties with Potential Impacts	None	7 Properties	12 Properties
Construction Easement Cost (Estimated)	\$0	\$287k	\$557k
Construction Cost (Estimated)	\$0	\$593k	\$986k