

Durbin Road

Public Right-of-Way Construction Impacts

Side: South (even-numbered homes)
Limits: Bradley Boulevard to Hopewood Street
Sidewalk Width: 5-Ft
Sidewalk Material: Concrete
Road Width: 26-Ft Curb to Curb

ADDRESS	CONSTRUCTION IMPACTS
Durbin Road at Hopewood Street	Construct an ADA ramp.
6128 Durbin Road, work on the side of the property along Durbin Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the concrete driveway apron. Remove the existing slate leadwalk within County's public right of way as needed and replace with concrete. Transition sidewalk behind utility pole, #764417-840840. Relocate guide wires.
6124 Durbin Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron.
6120 Durbin Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. Remove bushes and groundcover landscaping within County's public right of way as needed for sidewalk installation.
6116 Durbin Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. Remove two Zelkova trees, 4 and 3-inches in diameter; replacement trees will be planted. May need to adjust the Manhole cover.
6112 Durbin Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. Remove the existing slate leadwalk within County's public right of way and replace with concrete. Remove three trees, one 2-inches in diameter species unknown, one 14-inch in diameter Cherry tree and one 22-inch in diameter Crabapple tree that is in poor condition; replacement trees will be planted. Remove bushes and groundcover landscaping within County's public right of way as needed for sidewalk installation.

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

Durbin Road, SOUTH

ADDRESS	CONSTRUCTION IMPACTS
7012 Kenhill Road, work on the side of the property along Durbin Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. Remove eight trees, four Crape Myrtle trees 13, 9, 9 and 8 multi-stem, two Oak trees 6 and 13-inches in diameter, one 13-inch in diameter Magnolia tree and one 7-inch in diameter Linden tree; replacement trees will be planted. Remove bushes and groundcover landscaping within County's public right of way as needed for sidewalk installation.
Durbin Road at Kenhill Road	Construct two ADA ramps.
7017 Kenhill Road, work on the side of the property along Durbin Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. Remove shrubs, bushes and groundcover landscaping within County's public right of way as needed for sidewalk installation.
6004 Durbin Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. Transition sidewalk behind utility pole, #765418-560130. Relocate guide wires. Remove one 14-inch diameter Crabapple tree; replacement trees will be planted.
7108 Millwood Road, work on the side of the property along Durbin Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. Remove five Cherry trees, 12, 12, 7, 14, and 24-inches in diameter; replacement trees will be planted. Adjust the storm drain inlet top.
Durbin Road at Millwood Road	Construct two A.D.A. ramps. One ramp will need to be constructed around the utility pole #765418-700190.
7113 Millwood Road, work on the side of the property along Durbin Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Transition sidewalk in front of utility pole, #765418-820230. Remove and replace the existing concrete driveway apron. Remove shrubs, bushes and groundcover landscaping within County's public right of way as needed for sidewalk installation. Remove one, nine multi-stem Crape Myrtle tree; replacement trees will be planted. Adjust the storm drain inlet top. Adjust the in-ground green irrigation control box.

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

Durbin Road, SOUTH

ADDRESS	CONSTRUCTION IMPACTS
5900 Durbin Road, work on the side of the property along Durbin Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete and asphalt driveway apron. Remove two Cherry trees, 8 and 23-inches in diameter; replacement trees will be planted. Relocate the 15 MPH Speed Bump sign.
Durbin Road at Marbury Road	Construct two ADA ramps.
7109 Marbury Road, work on the side of the property along Durbin Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. The sidewalk will run in front of the utility pole, #765418-990300. Remove one 31-inch in diameter Cherry tree; replacement trees will be planted. Adjust the storm drain inlet top.
5824 Durbin Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. Transition sidewalk in front of utility pole, #766418-180370. Remove two trees, one 11-inch in diameter Goldenrain tree and one 7-inch in diameter Cherry tree; replacement trees will be planted.
5820 Durbin Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. Remove one 12-inch in diameter Goldenrain tree; replacement trees will be planted. Adjust the storm drain inlet top.
5816 Durbin Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. Transition sidewalk in front of utility pole. (Pole is not numbered).
5812 Durbin Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the two existing concrete driveway aprons. Remove two trees, one 10-inch in diameter Goldenrain tree and one 20-inch in diameter Cherry tree; replacement trees will be planted.
5808 Durbin Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. Remove two Goldenrain trees, 11 and 13-inches in diameter; replacement trees will be planted.
5804 Durbin Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. Remove the existing slate leadwalk within the County's public right of way and replace with concrete. Transition sidewalk in front of utility pole, #766418-510510. Remove two trees, one 10.5 multi-stem Crape Myrtle tree and one 4.5-inch in diameter Serviceberry tree; replacement trees will be planted. Remove bushes and groundcover landscaping within County's public right of way as needed for sidewalk installation. Adjust the storm drain inlet top.

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

Durbin Road, SOUTH

ADDRESS	CONSTRUCTION IMPACTS
5800 Durbin Road	<p>Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. Remove and replace the existing concrete leadwalk within County's public right of way as needed. Remove one 13-inch in diameter Linden tree; replacement trees will be planted. Adjust the Gas valve.</p>
Durbin Road at Radnor Road	<p>Construct two ADA ramps.</p>
5724 Durbin Road	<p>Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove the existing slate leadwalk within County's public right of way as needed and replace with concrete. Remove two trees, one 11-inch in diameter Oak tree and one 25-inch in diameter Cherry tree that is in poor condition; replacement trees will be planted. Adjust the storm drain inlet top.</p>
5720 Durbin Road	<p>Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. Adjust the storm drain inlet top.</p>
7316 Durbin Terr, work on the side of the property along Durbin Road	<p>Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove the existing asphalt driveway apron and replace with concrete. The sidewalk will run in front of the utility pole, #766418-9367. Adjust the Water meter.</p>
Durbin Road at Durbin Terrace	<p>Construct two ADA ramps.</p>
5710 Durbin Road	<p>Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove the existing slate leadwalk within County's public right of way and replace with concrete. Transition sidewalk behind utility pole, #767418-2067. Relocate guide wires.</p>
5706 Durbin Road	<p>Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace two concrete driveway aprons. Transition sidewalk behind utility pole, #767418-3068. Remove landscaping within County's public right of way as needed for sidewalk installation.</p>
5632 Bradley Blvd, work on the side of the property along Durbin Road	<p>Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. Remove and replace the existing concrete leadwalk within County's public right of way. Relocate the WSSC Air Valve Vent control box. Relocate the Stop sign and the Durbin Road and Bradley Blvd Street signs.</p>
Durbin Road at Bradley Boulevard	<p>Construction A.D.A. compliant ramp.</p>

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

Lenox Road

Public Right-of-Way Construction Impacts

Side: **North** (odd-numbered homes)
Limits: Millwood Road to Whittier Blvd
Sidewalk Width: 5-Ft
Sidewalk Material: Concrete
Road Width: 26-Ft Curb to Curb

ADDRESS	CONSTRUCTION IMPACTS
Lenox Road at Millwood Road	Construct an ADA ramp.
7000 Millwood Road, work on the side of the property along Lenox Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove the slate leadwalk within County's public right of way and replace with concrete. Remove landscaping and rocks within County's public right of way as needed for sidewalk installation.
County Easement	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-foot variable greenspace. Transition sidewalk behind storm drain inlet top. Remove three trees, two 18-inch in diameter Black Locust trees and one 26-inch in diameter White Pine tree; replacement trees will be planted.
7001 Kenhill Road, work on the side of the property along Lenox Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-foot variable greenspace. Remove and replace the existing concrete driveway apron. Relocate the Stop sign, Lenox Road and Kenhill Road street signs.
Lenox Road at Kenhill Road	Construct two A.D.A. compliant ramps, one around the utility pole #765417-220600.
7000 Kenhill Road, work on the side of the property along Lenox Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-foot variable greenspace. Remove and replace the existing concrete driveway apron.
6105 Lenox Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-foot variable greenspace. A retaining wall may be needed due to grade and elevation changes of the property. Remove and replace the existing concrete driveway apron. Adjust the storm drain inlet top.
6109 Lenox Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-foot variable greenspace. Remove and replace the existing concrete driveway apron. Remove two Pin Oak trees, 29 and 30-inches in diameter; replacement trees will be planted.

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

Lenox Road, NORTH

ADDRESS	CONSTRUCTION IMPACTS
7001 Hopewood Street, work on the side of the property along Lenox Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-foot variable greenspace.
Lenox Road at Hopewood Street	Construct two ADA ramps.
7000 Hopewood Street, work on the side of the property along Lenox Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-foot variable greenspace. Remove and replace the existing concrete driveway apron. Relocate in-ground basketball hoop. May need to adjust the storm drain inlet top. Adjust Water meter. Remove four Crape Myrtle trees with 12 multi-stems each; replacement trees will be planted.
7001 Whittier Blvd, work on the side of the property along Lenox Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-foot variable greenspace and tie into the existing sidewalk at the intersection of Lenox Road and Whittier Blvd. Remove and replace the existing ramp at the intersection to make ADA compliant.

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

Millwood Road

Public Right-of-Way Construction Impacts

Side: West (even-numbered side)

Limits: Plainview Road to Goldsboro Road/MD 614

Sidewalk Width: 5-Ft

Sidewalk Material: Concrete

Road Width: 26-Ft Curb to Curb

ADDRESS	CONSTRUCTION IMPACTS
Millwood Road at Plainview Road	Construct an ADA ramp.
7312 Millwood Road	Construct a 5-ft wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove the existing slate leadwalk within County's public right of way as needed and replace with concrete. The sidewalk will run in front of the utility pole, #765418-290720. Remove four Sugar Maple trees, 12, 18, 21 and 22-inches in diameter; replacement trees will be planted. Remove bushes and groundcover landscaping as needed for sidewalk installation.
7308 Millwood Road	Construct a 5-ft wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. Remove the existing slate leadwalk within the County's public right of way as needed and replace with concrete. Remove bushes and groundcover landscaping within County's public right of way as needed for sidewalk installation. Remove one 16-inch in diameter Cherry tree; replacement trees will be planted.
7304 Millwood Road	Construct a 5-ft wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. Remove the existing slate leadwalk within the County's public right of way as needed and replace with concrete. The sidewalk will run behind the utility pole, #765418-3857. The guide wires may need to be relocated. Adjust the Manhole cover. Remove one 19-inch in diameter Cherry tree; replacement trees will be planted.
7228 Millwood Court, work on the side of the property along Millwood Road	Construct a 5-ft wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. Remove the existing slate lead walk as needed and replace with concrete. Adjust the storm drain inlet top. Remove four trees, one 18-inch in diameter Linden tree, one 8-inch in diameter Swamp White Oak tree and two Redbud trees, 7 and 9-inches in diameter; replacement trees will be planted.
Millwood Road at Millwood Court	Construct two ADA ramps.

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

Millwood Road, WEST

ADDRESS	CONSTRUCTION IMPACTS
7208 Millwood Road	Construct a 5-ft wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove the existing slate leadwalk within County's public right of way as needed and replace with concrete.
7204 Millwood Road	Construct a 5-ft wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. Remove the existing slate leadwalk within County's public right of way as needed and replace with concrete. Adjust the storm drain inlet top. Remove two trees, one 32-inch in diameter Magnolia and one 24-inch in diameter White Pine; replacement trees will be planted.
7200 Millwood Road	Construct a 5-ft wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove the existing slate leadwalk within County's public right of way as needed and replace with concrete. Adjust the storm drain inlet top. Relocate the Stop sign and the Millwood Road and Durbin Road street signs. Remove two Linden trees, 20 and 21-inches in diameter; replacement trees will be planted.
Millwood Road at Durbin Road	Construct two ADA ramps.
7108 Millwood Road	Construct a 5-ft wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the two existing concrete driveway aprons. Remove five Cherry trees, 24, 14, 7, 12 and 12-inches in diameter; replacement trees will be planted. Remove bushes and landscaping rocks within County's public right of way as needed for sidewalk installation.
7104 Millwood Road	Construct a 5-ft wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. Remove bushes and groundcover landscaping within County's public right of way as needed for sidewalk installation. Remove two trees, one 28-inch in diameter Cherry tree and one 12-inch in diameter Red Maple tree; replacement trees will be planted.
7100 Millwood Road	Construct a 5-ft wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the two existing concrete driveway aprons. Remove hedges within County's public right of way as needed for sidewalk installation. Relocate the yellow Traffic Circle sign.
7008 Millwood Road	Construct a 5-ft wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. Remove one 2-inch in diameter Yellowwood tree; replacement trees will be planted.

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

Millwood Road, WEST

ADDRESS	CONSTRUCTION IMPACTS
7004 Millwood Road	<p>Construct a 5-ft wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. The sidewalk will run behind the utility pole, #765417-630570. The guide wires will need to be relocated.</p> <p>Remove bushes and landscaping rocks within County's public right of way as needed for sidewalk installation.</p>
7000 Millwood Road	<p>Construct a 5-ft wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. Remove bushes, groundcover landscaping and landscaping rocks within County's public right of way as needed for sidewalk installation.</p> <p>Remove 13 trees, one 6-inch in diameter Cherry tree, one 5-inch in diameter Mulberry tree, nine Spruce trees that are in poor condition, 12, 8, 10, 11, 10, 10, 10, 14 and 15-inches in diameter, and two Cherry trees 7 and 5.5-inches in diameter; replacement trees will be planted.</p>
Millwood Road at Lenox Road	<p>Construct two ADA ramps, one of which will need to be constructed around utility pole #765417-610510.</p>
6000 Lenox Road, work on the side of the property along Millwood Road	<p>Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. Remove two bushes within County's public right of way to allow for sidewalk installation.</p> <p>Adjust the Water meter.</p>
6920 Millwood Road	<p>Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. Remove the existing brick leadwalk within County's public right of way and replace with concrete.</p> <p>The sidewalk will run behind the utility pole, #765417-590350.</p> <p>Remove one 17-inch in diameter Cherry tree; replacement trees will be planted.</p>
6916 Millwood Road	<p>Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove the existing asphalt driveway apron and replace with concrete. Remove the existing slate leadwalk within County's public right of way and replace with concrete.</p> <p>Remove groundcover landscaping within County's public right of way as needed for sidewalk installation.</p> <p>Remove one 20-inch diameter Cherry tree; replacement trees will be planted.</p>
6912 Millwood Road	<p>Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. Remove the existing slate leadwalk within the County's public right of way as needed and replace with concrete.</p> <p>The sidewalk will run behind the utility pole, #765417-580190.</p> <p>Remove bushes and groundcover landscaping within County's public right of way as needed for sidewalk installation.</p> <p>Remove two trees, one 13-inch diameter Crabapple tree and one 8-inch diameter Magnolia tree; replacement trees will be planted.</p>

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

Millwood Road, WEST

ADDRESS	CONSTRUCTION IMPACTS
6908 Millwood Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. Remove the existing slate leadwalk within County's public right of way as needed and replace with concrete.
6904 Millwood Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. Remove two Cherry trees, one 18-inch in diameter that was previously marked for removal due to poor health, and one 14-inch in diameter; replacement trees will be planted.
6900 Millwood Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. The sidewalk will run behind the utility pole, #765417-570050. Remove groundcover landscaping within County's public right of way as needed for sidewalk installation.
6828 Millwood Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. The sidewalk will run behind the utility pole #765416-580900; guide wires will need to be relocated. Remove one 6-inch diameter Serviceberry tree; replacement trees will be planted.
6824 Millwood Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove the existing asphalt driveway apron and replace with concrete. The sidewalk will run in front of the utility pole #765416-600810. Remove bushes and groundcover landscaping within County's public right of way as needed for sidewalk installation.
6820 Millwood Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the two existing concrete driveway aprons. The sidewalk will run in front of utility pole, #765416-620710. Remove bushes and groundcover landscaping within County's public right of way as needed to allow for sidewalk installation. Adjust the Gas valve.
6818 Millwood Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove brick paver driveway apron and replace with concrete. Remove bushes and groundcover landscaping within County's public right of way as needed to allow for sidewalk installation. May need to adjust the Manhole cover. Remove one 33-inch diameter Cherry tree; replacement trees will be planted.
6816 Millwood Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. The sidewalk will run in front of the utility pole #765416-660620.
6808 Millwood Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron.

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

Millwood Road, WEST

ADDRESS	CONSTRUCTION IMPACTS
6804 Millwood Road	<p>Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the two existing concrete driveway aprons. The sidewalk will run behind the utility pole #765416-710480. Remove bushes and groundcover landscaping within County's public right of way as needed for sidewalk installation. Relocate Speed Bump sign.</p>
6800 Millwood Road	<p>Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. Remove the existing brick leadwalk within County's public right of way as needed and replace with concrete. The sidewalk will run behind the utility pole #765416-770340; the guide wires may need to be relocated. Remove one 13-inch diameter Cherry tree; replacement trees will be planted.</p>
6616 Millwood Road	<p>Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. Remove the existing slate leadwalk within County's public right of way as needed and replace with concrete. Remove bushes within County's public right of way as needed for sidewalk installation. Adjust the storm drain inlet top. Remove one 3-inch diameter Cherry tree; replacement trees will be planted.</p>
6612 Millwood Road	<p>Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. The sidewalk will run behind the utility pole #765416-800130. Remove bushes and groundcover landscaping within County's public right of way as needed for sidewalk installation. Adjust the Water meter.</p>
6608 Millwood Road	<p>Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. Remove three trees, one 15-inch diameter Callery Pear tree, and two Cherry trees, 7 and 2-inches in diameter; replacement trees will be planted.</p>
6604 Millwood Road	<p>Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the two existing concrete driveway aprons. Remove bushes and groundcover landscaping within County's public right of way as needed for sidewalk installation. Remove one 2.5-inch diameter Kwanzan Cherry tree; replacement trees will be planted.</p>
6600 Millwood Road	<p>Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. The sidewalk will run behind the utility pole #765415-770960. The guide wires will need to be relocated. Remove bushes and groundcover landscaping within County's public right of way as needed for sidewalk installation. Remove four trees, one 3-inch diameter Weeping Ornamental tree, two Willow Oak trees, 28- and 24-inches in diameter, one 3-inch diameter Variegated Dogwood tree; replacement trees will be planted.</p>

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

Millwood Road, WEST

ADDRESS	CONSTRUCTION IMPACTS
6518 Millwood Road	<p>Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. The sidewalk will run behind the utility pole #765415-720810; the guide wires will need to be relocated. Remove one 14-inch Littleleaf Linden tree; replacement trees will be planted.</p>
6516 Millwood Road	<p>Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. Remove shrubs and landscaping within County's public right of way as needed for sidewalk installation.</p>
6512 Millwood Road	<p>Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. The sidewalk will run behind the utility pole #765415-680670; the guide wires will need to be relocated. Adjust the Manhole cover.</p>
6508 Millwood Road	<p>Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. Remove groundcover landscaping within County's public right of way as needed for sidewalk installation. Relocate mailbox.</p>
6504 Millwood Road	<p>Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove and replace the existing concrete driveway apron. Remove the existing slate leadwalk within County's public right of way as needed and replace with concrete. Remove bushes and groundcover landscaping within County's public right of way as needed to allow for sidewalk installation.</p>
5901 Goldsboro Road, work on the side of the property along Millwood Road	<p>Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft variable greenspace. Remove the existing slate leadwalk within County's public right of way as needed and replace with concrete. Remove bushes and groundcover landscaping within County's public right of way as needed for sidewalk installation. The sidewalk will run in front of the brick Kenwood Park sign. Adjust the storm drain inlet top. Relocate the Stop sign and the Millwood Road and Goldsboro Road street signs. Remove three trees, one 21-inch diameter Black Cherry tree that is in poor condition, one 9-inch diameter Sugar Maple tree and one 16-inch diameter Holly tree; replacement trees will be planted.</p>
Millwood Road at Goldsboro Road	<p>Construct an ADA ramp.</p>

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

Kenhill Road

Public Right-of-Way Construction Impacts

Side: West (even-numbered side)
Limits: Durbin Road to Highboro Drive
Sidewalk Width: 5-Ft
Sidewalk Material: Concrete
Road Width: 26-ft Curb to Curb

ADDRESS	CONSTRUCTION IMPACTS
Durbin Road at Kenhill Road	Construct an ADA ramp.
7012 Kenhill Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft-wide variable greenspace. Remove paver leadwalk within County's public right of way and replace with concrete as needed. Remove bushes and landscaping within County's public right of way as needed for sidewalk installation. Remove tree stump. A retaining wall may be needed. Remove five trees, two Crape Myrtles, 9 and 11-inches in diameter, two Dogwood trees, 14 and 2-inches in diameter, and one 16-inch diameter Oak tree; replacement trees will be planted. (See also impacts to side yard along Durbin Road in the Durbin Road Right of Way Construction Impacts, Page 2 above)
7008 Kenhill Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft-wide variable greenspace. Remove asphalt driveway apron and replace with concrete. Remove four trees, three Cherry trees, 4, 5.5 and 11-inches in diameter, and one 14-inch diameter Sugar Maple tree; replacement trees will be planted.
7004 Kenhill Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft-wide variable greenspace. Remove asphalt driveway apron and replace with concrete driveway apron. Remove two 8 and 9-inch diameter Cherry trees; replacement trees will be planted.
7000 Kenhill Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft-wide variable greenspace. Remove paver leadwalk within County's public right of way and replace with concrete. Place sidewalk in front of fire hydrant. Adjust storm drain top. Relocate stop sign and permit park signs. Remove two 18- and 12-inch diameter Cherry trees; replacement trees will be planted.

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

Kenhill Road, WEST

ADDRESS	CONSTRUCTION IMPACTS
Kenhill Road at Lenox Road	Construct two ADA ramps.
6100 Lenox Road, work on side of property along Kenhill Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft-wide variable greenspace. Remove and replace concrete driveway apron. Remove bushes and landscaping within County's public right of way as needed for sidewalk installation. Remove two Cherry trees, 13- and 14-inches in diameter; replacement trees will be planted.
6720 Kenhill Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft-wide variable greenspace. Remove and replace concrete driveway apron. Remove bushes within County's public right of way as needed for sidewalk installation. Remove two trees, one 28-inch diameter Cherry tree, and one 10-inch diameter Southern Magnolia tree; replacement trees will be planted.
6716 Kenhill Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft-wide variable greenspace. Remove bushes and landscaping within County's public right of way as needed for sidewalk installation. Remove and replace concrete driveway apron. Place sidewalk behind Optical Fiber Network box. Remove one 41-inch diameter Cherry tree; replacement trees will be planted.
6712 Kenhill Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft-wide variable greenspace. Remove and replace concrete driveway apron. Remove landscaping within County's public right of way as needed for sidewalk installation. Remove two trees, one 18-inch diameter Locust tree and one 17-inch diameter Cherry tree; replacement trees will be planted.
6708 Kenhill Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft-wide variable greenspace. Remove and replace concrete driveway apron. Place sidewalk behind fire hydrant.
6101 Eastview Street, work on side of property along Kenhill Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft-wide variable greenspace. Adjust storm drain top.
Kenhill Road at Eastview Street	Construct two ADA ramps.
6100 Eastview Street, work on side of property along Kenhill Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft-wide variable greenspace. Place sidewalk in front of Verizon box

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

Kenhill Road, WEST

ADDRESS	CONSTRUCTION IMPACTS
6620 Kenhill Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft-wide variable greenspace. Remove and replace two concrete driveway aprons.
6616 Kenhill Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft-wide variable greenspace. Remove and replace concrete driveway apron.
6612 Kenhill Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft-wide variable greenspace. Remove and replace concrete driveway apron. Remove bushes and landscaping within County's public right of way as needed for sidewalk installation. Remove paver leadwalk within County's public right of way and replace with concrete. Place sidewalk in front of Optical Fiber Network box.
6608 Kenhill Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft-wide variable greenspace. Remove and replace concrete driveway apron. May need to relocate Light Pole No. 06009 for the sidewalk to run in front.
6604 Kenhill Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft-wide variable greenspace. Remove and replace concrete driveway apron. Remove bushes and landscaping within County's public right of way as needed for sidewalk installation. Place sidewalk in front of optical fiber network box.
6600 Kenhill Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft-wide variable greenspace. Remove and replace concrete driveway apron.
6528 Kenhill Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft-wide variable greenspace. Remove and replace concrete driveway apron. Adjust storm drain top. Remove two Crape Myrtle trees, 19 and 20-inches in diameter; replacement trees will be planted.
6522 Kenhill Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft-wide variable greenspace. Remove and replace concrete driveway apron. The sidewalk will run behind utility Pole No. 06007. Place sidewalk behind optical fiber network box. Adjust the in-ground Verizon telecom box. Adjust the manhole cover.
6516 Kenhill Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft-wide variable greenspace. Remove and replace concrete driveway apron.

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

Kenhill Road, WEST

ADDRESS	CONSTRUCTION IMPACTS
6512 Kenhill Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft-wide variable greenspace. Remove and replace concrete driveway apron. Remove paver leadwalk within County's public right of way and replace with concrete.
6508 Kenhill Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft-wide variable greenspace. Remove and replace two concrete driveway aprons. Place sidewalk in front of optical fiber network box.
6504 Kenhill Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft-wide variable greenspace. Remove and replace concrete driveway apron. Adjust storm drain top. Remove one 13-inch diameter Cherry tree; replacement trees will be planted.
6500 Kenhill Road	Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft-wide variable greenspace. Remove and replace concrete driveway apron. Adjust storm drain top. Place sidewalk behind fire hydrant.

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

Highboro Drive

Public Right-of-Way Construction Impacts

Side: Northeast (odd-numbered side)

Limits: Kenhill Road to Whittier Drive

Sidewalk Width: 5-Ft

Sidewalk Material: Concrete

Road Width: 26-ft Curb to Curb

ADDRESS	CONSTRUCTION IMPACTS
6001 Highboro Drive	<p>Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft-wide variable greenspace. The sidewalk will run behind utility Pole No. 765415-050650; Pole supporting cable may be relocated. Remove and replace two concrete driveway aprons. Adjust storm drain top. Remove three Cherry trees, 21, 24, and 20-inches diameter; replacement trees will be planted.</p>
6001 Shady Oak Lane, work on side of property along Highboro Drive	<p>Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft-wide variable greenspace. Remove and replace concrete driveway apron. Remove paver leadwalk within County's public right of way and replace with concrete. Remove bushes and landscaping within County's public right of way. Adjust the manhole cover. Remove two trees, one 1-inch diameter species tree and one 2-inch diameter Tree Hydrangea; replacement trees will be planted.</p>
Highboro Drive at Shady Oak Lane	<p>Construct two ADA ramps.</p>
6000 Shady Oak Lane, work on side of property along Highboro Drive	<p>Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft-wide variable greenspace. Remove one 9-inch diameter Cherry tree; replacement trees will be planted.</p>
6105 Highboro Drive	<p>Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft-wide variable greenspace. Remove and replace concrete driveway apron. Remove paver leadwalk within County's public right of way and replace with concrete. Remove bushes within County's public right of way as needed. Remove two trees, one 51-inch Willow Oak and one 23-inch Cherry tree; replacement trees will be planted.</p>

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

Highboro Drive, NORTHEAST

ADDRESS	CONSTRUCTION IMPACTS
6109 Highboro Drive	<p>Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft-wide variable greenspace.</p> <p>Remove and replace two concrete driveway aprons.</p> <p>Remove bushes and landscaping within County's public right of way as needed.</p> <p>Place sidewalk behind fire hydrant.</p> <p>Remove one 17-inch diameter Cherry tree; replacement trees will be planted.</p>
6113 Highboro Drive	<p>Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft-wide variable greenspace.</p> <p>Remove and replace two concrete driveway aprons.</p> <p>Remove bushes and landscaping within County's public right of way.</p>
6117 Highboro Drive	<p>Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft-wide variable greenspace.</p> <p>Remove and replace concrete driveway apron.</p> <p>Remove paver leadwalk within County's public right of way and replace with concrete.</p> <p>Remove two trees, one 6-inch diameter Elm tree and one 18-inch diameter Cherry tree; replacement trees will be planted.</p>
6121 Highboro Drive	<p>Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft-wide variable greenspace.</p> <p>Remove and replace concrete driveway apron.</p> <p>Remove paver leadwalk within County's public right of way and replace with concrete.</p> <p>Remove two Cherry trees, 3 and 4-inches in diameter; replacement trees will be planted.</p>
6609 Whittier Boulevard, work on side of property along Highboro Drive	<p>Construct a 5-ft-wide concrete sidewalk with a 0 to 3-ft-wide variable greenspace.</p> <p>Adjust storm drain top.</p> <p>Remove two Cherry trees, 31- and 16-inches in diameter; replacement trees will be planted.</p>
Highboro Drive at Whittier Boulevard	<p>Remove and replace ADA ramp.</p>

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.