BARRON STREET
Right of Way Construction Impacts
Improvement Item No. 014A4350

Side: Northeast / Odd Numbered Side
Limits: Carroll Avenue to Prospect Street
Sidewalk Width: 5-foot-wide
Sidewalk Material: Concrete
Roadway Width: 22-feet

ADDRESS	CONSTRUCTION IMPACTS
8001 Baron Street	Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Begin new sidewalk at existing ADA ramp at Carroll Avenue. Remove and replace concrete leadwalk within the County's public right of way. Remove asphalt driveway apron within County's public right of way and replace with concrete. Adjust storm drain top. Relocate street sign. Transition sidewalk behind utility pole 801420-580870. Note: Box on utility pole may need to be relocated. Transition sidewalk in front of fire hydrant. Remove shrubs, as needed.
8003 Baron Street	Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Remove and replace concrete leadwalk and steps within the County's public right of way. Remove asphalt driveway apron within County's public right of way and replace with concrete.
8005 Baron Street	Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Remove asphalt driveway apron within County's public right of way and replace with concrete. Remove and replace concrete leadwalk within the County's public right of way. Relocate street sign. Transition sidewalk in front of utility pole 801420-540900.

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

ADDRESS	CONSTRUCTION IMPACTS
8007 Baron Street	Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Remove asphalt driveway apron within County's public right of way and replace with concrete. Remove and replace concrete leadwalk and steps within the County's public right of way.
8009 Baron Street	Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Remove and replace concrete driveway apron. Remove and replace concrete leadwalk within the County's public right of way. Transition sidewalk in front of utility pole 801420-340930.
8011 Baron Street	Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Remove and replace concrete driveway apron. Remove and replace concrete leadwalk within the County's public right of way.
8013 Baron Street	Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Remove and replace concrete driveway apron. Adjust water meter in driveway apron. Transition sidewalk in front of utility pole 801421-210000.
8015 Baron Street	Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace Remove and replace concrete driveway apron. Remove brick leadwalk within County's public right of way and replace with concrete.
8017 Baron Street	Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Remove and replace concrete driveway apron. Remove asphalt driveway apron within County's public right of way and replace with concrete.
8019 Baron Street	Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Remove asphalt driveway apron within County's public right of way and replace with concrete. Remove asphalt leadwalk within County's public right of way and replace with concrete. Transition sidewalk in front of utility pole 801421-080100.

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

ADDRESS	CONSTRUCTION IMPACTS
8021 Baron Street	Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Adjust storm drain top. Construct A.D.A. compliant ramp at Prospect Street. Relocate street sign. Remove asphalt driveway apron within County's public right of way and replace with concrete. Remove slate leadwalk within County's public right of way and replace with concrete. Transition sidewalk in front of utility pole 801421-0314.

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

GLENSIDE DRIVE

Right of Way Construction Impacts

Improvement Item No. 014A4351

Side: East / Odd Numbered Side
Limits: Carroll Avenue to Prospect Street
Sidewalk Width: 5-foot-wide
Sidewalk Material: Concrete
Roadway Width: 19-feet

ADDRESS	CONSTRUCTION IMPACTS
8001 Glenside Drive	Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace. Begin new sidewalk at existing ADA ramp at Carroll Avenue. Remove and replace concrete driveway apron. Transition sidewalk in front of utility pole. Remove and replace concrete leadwalk and step within the County's public right of way. Remove shrubs, as needed. Relocate street sign. Transition in front of utility pole 801420-580530.
8003 Glenside Drive	Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace. Remove and replace concrete driveway apron. Remove and replace concrete leadwalk and steps within the County's public right of way.
8005 Glenside Drive	Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace. Remove asphalt driveway apron within County's public right of way and replace with concrete. Transition sidewalk in front of utility pole 801420-370620. Remove and replace concrete leadwalk within the County's public right of way.
8007 Glenside Drive	Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace. Remove brick driveway apron within County's public right of way and replace with concrete. Remove brick leadwalk within County's public right of way and replace with concrete. Remove and replace concrete steps within the County's public right of way.

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

ADDRESS	CONSTRUCTION IMPACTS
8009 Glenside Drive	Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace. Remove and replace concrete driveway apron. Transition sidewalk in front of utility pole 801420-260660.
8011 Glenside Drive	Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace. Remove and replace concrete driveway apron. Remove and replace concrete leadwalk within the County's public right of way.
8013 Glenside Drive	Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace. Remove asphalt driveway apron within County's public right of way and replace with concrete. Transition sidewalk in front of utility pole 801420-150720. Remove shrubs, as needed.
8015 Glenside Drive	Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace. Remove and replace concrete driveway apron. Remove and replace concrete leadwalk within the County's public right of way.
8017 Glenside Drive	Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace. Remove and replace concrete driveway apron. Transition sidewalk in front of utility pole 801420-040780. Remove and replace concrete leadwalk within the County's public right of way. Remove shrubs, as needed.
8019 Glenside Drive	Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace. Remove and replace concrete driveway apron. Construct a block retaining wall along front of property, if needed.
8021 Glenside Drive	Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace. Remove brick driveway apron within County's public right of way and replace with concrete. Remove brick parking area along front of property, as needed. Transition sidewalk in front of utility pole 800420-960870.

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

ADDRESS	CONSTRUCTION IMPACTS
8023 Glenside Drive	Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace. Remove and replace concrete leadwalk within the County's public right of way. Adjust water meter. Remove asphalt driveway apron within County's public right of way and replace with concrete. Transition sidewalk in front of fire hydrant. Remove shrubs, as needed.
8025 Glenside Drive	Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace. Remove asphalt driveway apron within County's public right of way and replace with concrete. Remove slate driveway apron within County's public right of way and replace with concrete. Remove large decorative stones, as needed. Transition sidewalk in front of two utility poles 800420-8998. Remove brick flower bed curb, as needed.
8027 Glenside Drive	Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace. Adjust storm drain top. Relocate street sign. Remove asphalt driveway apron within County's public right of way and replace with concrete. Remove shrubs, as needed. Construct A.D.A. compliant ramp at Prospect Street.

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

LONG BRANCH PARKWAY
Right of Way Construction Impacts
Improvement Item No. 014A4353

Side: West / Even Numbered Side
Limits: Carroll Avenue to Patterson Ct.
Sidewalk Width: 5-foot-wide
Sidewalk Material: Concrete
Roadway Width: 20-feet

ADDRESS	CONSTRUCTION IMPACTS
7822 Carroll Avenue (Long Branch Parkway Side of Property)	Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace. Start new sidewalk at existing ADA ramp on Carroll Avenue. Adjust two manholes. Adjust telecommunications box top. Transition sidewalk behind traffic light pole. Box on traffic light pole may need to be relocated. Transition sidewalk behind utility pole 801420-270200 and guywire. Relocate street sign. Transition sidewalk behind fire hydrant. Remove and replace concrete driveway apron.
7902 Long Branch Parkway	Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace. Adjust storm drain top. Remove and replace concrete driveway apron. Remove and replace concrete leadwalk within the County's public right of way. Transition sidewalk in front of utility pole 801420-180270. Transition sidewalk in front of utility pole 801420-140300. Remove decorative stones.
7904 Long Branch Parkway	Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace. Remove and replace concrete leadwalk within the County's public right of way.

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

ADDRESS	CONSTRUCTION IMPACTS
7906 Long Branch Parkway	**Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace.** **Remove and replace concrete leadwalk within the County's public right of way.** **Transition sidewalk in front of utility pole 801420-060350.** **Adjust storm drain top.** **Relocate sign.** **Construct A.D.A. compliant ramp at Patterson Court.**

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

CHESTER STREET
Right of Way Construction Impacts
Improvement Item No. 014A4349

Side: East / Odd Numbered Side
Limits: Carroll Avenue to Prospect Street
Sidewalk Width: 5-foot-wide
Sidewalk Material: Concrete
Roadway Width: 26-feet

ADDRESS	CONSTRUCTION IMPACTS
8101 Chester Street	Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace. Begin new sidewalk at existing ADA ramp. Construct a block retaining wall along front of property, if needed. Remove and replace concrete driveway apron. Adjust storm drain top. Relocate two street signs.
8105 Chester Street	Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace. Construct a block retaining wall along front of property, if needed. Remove and replace two concrete driveway aprons. Remove shrubs, as needed.
8107 Chester Street	Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace. Remove brick retaining wall within the County's public right of way and replace with a block retaining wall, if needed. Remove and replace concrete driveway apron.
8109 Chester Street	Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace. Construct a block retaining wall along front of property, if needed. Remove and replace concrete driveway apron. Remove shrubs, as needed. Relocate street sign. Trim low hanging tree limbs, as needed.

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

ADDRESS	CONSTRUCTION IMPACTS
8111 Chester Street	Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace. Construct a block retaining wall along front of property, if needed. Remove and replace concrete driveway apron. Remove PVC property drain pipe within the County's public right of way, if needed. Transition sidewalk behind fire hydrant. Remove concrete parking area within the county's public right of way.
8113 Chester Street	Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace. Construct a block retaining wall along front of property, if needed. Remove and replace concrete driveway apron. Remove shrubs, as needed. Relocate street sign.
8115 Chester Street	Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace. Construct a block retaining wall along front of property, if needed. Remove and replace concrete driveway apron. Remove shrubs, as needed.
8117 Chester Street	Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace. Construct a block retaining wall along front of property, if needed. Remove and replace two concrete driveway aprons.
1211 Prospect Street (Chester Street side of property)	Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace. Construct a block retaining wall along front of property, if needed. Relocate street sign. Construct A.D.A. compliant ramp at Prospect Street.

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

PROSPECT STREET
Right of Way Construction Impacts
Improvement Item No. 014A4348

Side: West / Even Numbered Side
Limits: East end to Long Branch path
Sidewalk Width: 5-foot-wide
Sidewalk Material: Concrete
Roadway Width: 26-feet

ADDRESS	CONSTRUCTION IMPACTS
1214 Prospect Street	Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace. Remove and replace concrete driveway apron. Begin new sidewalk at driveway apron. Remove and replace block retaining wall along driveway apron.
1212 Prospect Street	Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace. Remove and replace concrete and brick driveway apron. Construct a block retaining wall along front of property, if needed. Remove shrubs, as needed. Transition sidewalk behind utility pole 801421-030480.
1210 Prospect Street	Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace. Remove and replace concrete driveway apron. Construct a block retaining wall along front of property, if needed.
1208 Prospect Street	Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace. Remove and replace concrete driveway apron. Transition sidewalk behind utility pole 801421-0034.
1206 Prospect Street	Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace. Remove and replace concrete driveway apron.
1204 Prospect Street	Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace. Remove and replace concrete driveway apron. Transition sidewalk behind utility pole 800421-920220. Relocate guy wire.

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

ADDRESS	CONSTRUCTION IMPACTS
1200 Prospect Street	Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace. Remove and replace concrete driveway apron. Transition sidewalk behind utility pole 800421-810130. Construct a block retaining wall along front of property, if needed. Remove shrubs, as needed.
1000 Prospect Street	Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace. Remove asphalt driveway apron within County's public right of way and replace with concrete. Remove and replace concrete leadwalk within the County's public right of way. Remove and replace concrete steps within the County's public right of way. Remove shrubs, as needed. Remove brick retaining wall within the County's public right of way, as needed. Transition sidewalk to existing asphalt path leading to Long Branch bridge. Replace asphalt path to bridge, if needed.

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.